

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- FRANK TAYLOR
 Farm- Nixon No. 3


SEC. 10 T. 33 R. 3E
 N/2 S/2 SE/4
 (1320' from EL & 805' from SL of SE/4)

Total Depth. 3246'
 Comm. 6-27-57 Comp. 7-3-57
 Shot or Treated.

County Cowley
 KANSAS

Contractor. Criswell Drilling Company

Issued. 10-26-57



CASING:

8 5/8" 129' cem. w/125 sx
 4 1/2" 3237' cem. w/75 sx

Elevation. 1162 DF

Production. 141 BOPD

Figures indicate Bottom of Formations.

surface sand & gravel	100	
lime & shale	200	
lime & shale	410	
lime & shale	615	
shale W/Lime streaks	885	
shale & shells	1225	
shale	1450	
lime & shale streaks	1535	
shale & lime	1750	
lime & shale	1950	
shale	2205	
shale W/Sand	2268	
sand	2415	
shale & lime streaks	2565	
shale	2599	
sand	2671	
shale	2710	
shale	2779	
lime	2865	
lime & shale	2955	
lime	2985	
lime	3085	
lime & shale	3105	
shale	3200	
shale	3235	
chat	3246	RTD
Total Depth		

TOPS:

Stalnaker sand	2268
Layton sand	2599
Kansas City	2779
Oswego	2955
Base Oswego	3069
No Bartlesville	
Mississippi	3235

D.S.T. 3236'-3246'. Open 1 hr. Rec.
 Muddy oil BHP 1005#/30