

SINCLAIR PRAIRIE OIL CO.
 H.M. Detmer No. 12


SEC. 24 T. 32 R. 4E
 CEL NW SW
 660' fr NL 1100' fr WL

Total Depth. 3032, P.B. 3028
 Comm. 12-10-36 Comp. 1-19-37
 Shot or Treated.
 Contractor.
 Issued. 2-27-37

County Cowley.

CASING.

15 1/8" 377'
 12 1/8" 885'
 10" 1725'
 8 1/2" 2130'
 6 5/8" 2948'



Elevation.

Production. 15 B.O.

Figures Indicate Bottom of Formations.

no wtr.

cellar	8	shale and lime	1365
lime and shale	40	shale	1375
lime 1BWFH	97	lime and shale	1420
red rock	102	lime	1430
lime and shale	118	shale	1468
lime	135	lime sdy	1482
red rock	141	lime and shale	1582
lime and shale	185	shale	1620
red rock	203	lime and shale	1645
lime and shale	220	lime	1660
lime sholly & shaly	240	shale light	1700
lime	255	shale and lime	1725
red rock	266	shale	1830
lime	270	lime and shale	1855
shale	285	sand	1870
lime and shale	310	11 BWFHR 1860	
lime	330	lime sdy	1918
red rock	355	shale	1935
shale	360	lime	1940
red rock	365	sand HFW 1940-75	1975
lime and shale	400	shale	2058
lime	415	lime	2061
shale and lime	435	sand water 2070-88	2088
lime	475	shale	2090
shale and lime	490	lime sdy	2130
lime	505	shale	2318
shale and lime	520	sand 1 1/2 BW 2345	2345
shale dark	526	lime sdy	2398
lime	540	lime sdy	2428
shale	585	shale	2483
lime	592	lime	2520
shale	622	shale	2525
lime sdy	645	lime	2583
Gas est 1 MCFT 630-40		shale	2593
shale	660	lime	2598
lime	664	shale and shells	2611
shale	755	shale	2672
lime and shale	775	lime	2695
shale and lime sdy	800	shale	2710
sand broken HFW 820	845	lime	2745
shale sdy	875	shale	2754
lime	885	lime	2775
lime sdy	905	shale	2783
shale blue	910	lime sdy	2788
lime and shale	980	shale	2924
lime broken	992	red rock	2949
shale and lime	1095	shale sdy	2965
lime and shale	1240	sand	2978
lime broken	1250	shale sdy	2985
lime	1280	sand	3028
shale dark	1285	lime	3032

Total Depth. Top B'Ville 2948
 Base " " 3030
 Well drilled to 3032 in lime below
 Bartlesville & P.B. to 3028