


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- SINCLAIR OIL & GAS
 Farm- C.H. Kukuk "South" No. 80

SEC. 24 T. 32 R. 4E
 NW SE NE
 330' fr NL & 990' fr EL
 of S $\frac{1}{2}$ NE $\frac{1}{4}$
 County Cowley
 KANSAS

CORRECTED LOG.

Total Depth. 3032' PB 2991'
 Comm. 7-2-54 Comp. 7-11-54
 Shot or Treated.
 Contractor. H & H Drlg. Co.
 Issued. 10-23-54



Elevation. 1255' RE

Production. 10 bbls./125 BW 24 hr

CASING:

10 3/4" 103' w/125 sx cem.
 7" 2984' w/150 sx cem.

Figures Indicate Bottom of Formations.

soil	10	TOPS:	
lime	190	Layton	2340
lime-shale	360	Kansas City	2490
red rock	395	Bartlesville sand	2955
lime-shale	575	Mississippi	3031
shale-shells	675		
shale	890		
shale-lime	1482		
sand	1507		
shale	1588		
lime	1604		
shale-sdy shale	1660		
lime	1678		
shale-sdy shale	1737		
lime-shale	1894		
sand	1917		
shale-sdy shale	1936		
sand	2012		
shale	2090		
lime-shale	2105		
sand-sdy shale	2146		
shale	2340		
sand-sdy shale	2432		
shale	2490		
shaley lime	2504		
lime	2590		
shale-shaley lime	2610		
sand-sdy shale	2667		
shale-lime	2808		
shaley-silty sand	2865		
limey shale	2918		
limey-sdy shale	2953		
shaley sand	2983		
sand	3030		
lime	3032		3
Total Depth			

Treated w/Dowell oil-sand
 fracture 2 times-acid 8000# &
 4000# R 20-40 sand

~~7-16-54 - 2984-3029' - 4000~~
~~gals. - load oil 199 bbls.~~

Oil-sand frac by Dowell Incorporated-
 Poor-Went to wtr.

3-6-54-2984-2991 -2000 gals.
 load oil 125 bbls.

Oil -sand frac by Dowell Incor-
 porated-Fair-quite a lot of wtr.