

KANSAS CORPORATION COMMISSION


27-16-26W

WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

API # 15-135-206

L




Lease Name: Dooner "A" Well No. 1
 Well Located: C NE NE
Ness County SEC 27 TWP 16S RGE 26W
 Operator: Pickrell Drilling Company
 Address: 705 Fourth National Bank Bldg., Wichita, Kansas
 Elevation: Ground 2621 D.F. 2623 K.B. 2626
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 6/1/ 1972 Drilling Completed: 6/11 1972
 Well Completed: 19 Total Depth 4585'
 Initial Production: _____

Casing Record

Size: 8-5/8" Set at 261' Size: _____
 Size: _____ Set at _____ Size: _____



Run 7 Jts. 8-5/8" surface casing set @ 261' KB. Cemented
 Liner Rec'd w/150 sacks. Completed 6:15 P.M. Circulated.

Size: _____ No oil string run. D & A. Plugged down 3:15 P.M. June 11, 1972.

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>150</u>	<u>3/2</u>
_____	_____	_____
_____	_____	_____

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

No log run on this well.



27-16-26w

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom
Surface. Soil	0	40
Shale & Shells	40	263
Shale	263	1575
Sand	1575	1765
Shale & Sand Stringers	1765	1790
Shale	1790	2018
Anhydrite	2018	2060
Shale	2060	2485
Shale - Lime	2485	2790
Lime	2790	2940
Shale & Lime	2940	3260
Lime & Shale	3260	3405
Shale & Lime	3405	3735
Lime & Shale	3735	3855
Shale & Lime	3855	4040
Lime	4040	4397
Lime & Shale	4397	4475
Lime	4475	4505
Lime & Shale	4505	4575
Lime	4575	4580
Miss., & RTD	4580	4585

DST # 1 4560-4575: Open 50" rec. 25' mud
w/oil spots. SIP's 41#/30" to 41#/30".
FP's 31# to 31#.

DST # 2 4575-4585: Open 2 hours, 20", rec. 430' muddy
salt water, no show of oil. SIP's 1164#/30" to
1099#/60", FP's 52#-187#.

C.F.S.

4490

4575

4585

S.L.M.

4508.43

4507.93

.50 Difference

Board
Strap

Slope Tests

2000

2500

3000

3500

4000

4500

SAMPLE TOPS

SC	2018
B SC	2060
HEEB	3914
LANS	3953
STARK	4202
BKC	4258
MARM	4302
PAWN	4397
FT SC	4463
CHER	4487
MISS LM	4553
MISS DOL	4564
TD	4585