

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


26-32-4E

Company- BOWMAN & GRISMORE  
Farm- Goode No. 1

SEC. 26 T. 32 R. 4E  
SE SE NE

Total Depth. 3077'  
Comm. 10-15-53 Comp. 10-25-53  
Shot or Treated.  
Contractor. Kriswell Drhg. Co.  
Issued. 7-17-54

County Cowley  
KANSAS



Elevation. 1209' K B

Production. Pmp. 25/ no wtr

CASING:

8 5/8" 128'  
5 1/2" 3077'

Figures Indicate Bottom of Formations.

soil	5
clay-shale	20
lime	340
lime-shale brkn	450
red bed	465
lime	480
shale-lime strks	570
shale	607
lime-shale	880
lime	895
shale-lime strks	1175
sdv shale	1230
shale-lime	1375
shale sdv	1454
sand	1467
sand-shale	1510
sdv shale	1577
lime-shale	1620
shale	1645
shale-sdv shale	1682
lime	1700
shale-lime sdv	1743
sand	1758
lime-sand w/shale	1820
shale	1894
lime	1900
shale	1913
sand	1995
sdv shale-shale	2114
lime	2121
shale	2129
sand	2134
shale-lime	2270
shale	2361
sand	2426
shale-lime strks	2520
lime	2564
shale	2572
lime	2622
shale-lime	2785
lime	2830
shale-lime	2931
sdv shale	2943
sand	2957
sdv shale-shale	3057
lime	3077
Total Depth	

TOPS: Scout	
Peacock sand	1452
Upper Hoover	1740
Lower Hoover	1781
Layton	2359
Kansas City	2517
Cherokee	2825
Bartlesville	2936
Mississippi	3055

2825  
Ch-1618