

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


26-32-4E

Company- EARL F. WAKEFIELD & EUCLIAN WALKER
Farm- Thirsk No. 3

SEC. 26 T. 32 R. 4E
SE NE SE

Total Depth. 2902'
Comm. 4-2-54 Comp. 4-9-54
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 5-15-54

County Cowley
KANSAS



Elevation. 1182' RB

Production. Pmp. 25 & no wtr.

Figures indicate Bottom of Formations.

| CASING: | |
|-------------------------|----------|
| 10 3/4" | 79' |
| 7" | 2898' |
| surface | 80 |
| lime | 265 |
| lime & shale stks | 305 |
| lime | 410 |
| lime & shale stks | 478 |
| shale & shells | 695 |
| shale & lime stks | 1600 |
| shale & lime | 1690 |
| shale | 1710 |
| sand (Hoover) | 1735 |
| shale & sand | 1740 |
| shale | 1767 |
| shale & lime stks | 1916 |
| sand (Stalnaker, Upper) | 1951 |
| shale | 2005 |
| sand (Stalnaker, Lower) | 2030 |
| shale & lime | 2103 |
| shale & lime stks | 2109 |
| sand | 2135 |
| shale & sand | 2140 |
| shale & lime stks | 2194 |
| shale | 2336 |
| sand | 2401 |
| shale & lime | 2454 |
| shale & lime stks | 2465 |
| shale | 2499 |
| lime (Top K. C.) | 2645 |
| lime & shale | 2690 |
| lime | 2700 |
| shale & lime stks | 2731 |
| lime | 2740 |
| lime & shale | 2760 |
| shale | 2770 |
| shale & lime | 2875 |
| shale | 2898 |
| sand | 2902 RTD |
| Total Depth | |

| Tops: | |
|-----------------|------|
| Hoover | 1710 |
| Stalnaker Upper | 1916 |
| Stalnaker Lower | 2005 |
| Kansas City | 2499 |