


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- WHITE & ELLIS DRILLING, INC., ET AL  
Farm- Slaybaugh No. 1

SEC. 21 T. 30 R. 1E  
NW NE SE

Total Depth. 3845'  
Comm. 3-5-57 Comp. 3-24-57  
Shot or Treated.  
Contractor. White & Ellis Drilling, Inc.,  
Issued. 5-11-57

County Sumner KANSAS



CASING:

8 5/8" @190' w/180 sx cem.

Elevation. 1237' RB

Production. Dry

Figures indicate Bottom of Formations.

Kelly bushing measurements 5' above ground level.

sand & shale	150
Anhydrite	370
shale	490
shale & lime	760
lime	865
shale & lime	925
lime	1075
shale	1280
lime	1550
shale	1640
lime	1680
shale	1750
lime	1885
shale & lime	1910
lime	2120
lime & shale	2306
lime	2310
shale & lime	2466
Top of Stalnaker	
shale & sand	2512
sand	2530
shale	2645
shale & lime	2760
shale	2769
Top of Kansas City	
lime	3020
lime & shale	3068
shale (sandy)	3098
lime & shale	3200
shale	3389
Top of Mississippi	
lime & chert	3477
lime (Mississippi)	3738
shale & lime	3780
Top of Kinderhook	
shale	3841
Top of Simpson	
sand	3845
Total Depth	

SCOUT TOPS	
Stalnaker	2466
Kansas City	2769
Base/Kansas City	3017
Conglomerate	3345
Mississippi	3389
Kinderhook	3780
Simpson	3841