

PHONE HE 1-1940 CHANUTE  
PHONE TE 8-3601 WICHITA

Well Record

119 S. GRANT, CHANUTE KANSAS  
5706 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. Q-29 Farm Friedline "B-C" Producer Schermerhorn Oil Corp.  
 Location Sec. 17 Twp. 28 Rg. 17E  
 Elevation State Kansas County Wilson  
 Kind (Oil, Gas, Water, Dry Hole) Contractor Sutcliffe Pipe & Supply  
 Producing formation Top Bottom  
 Shot with qts. from to  
 Packer set at Kind Size  
 Liner from to Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
15	Soil-Lime Rock & clay	15			
89	Shale	104			
10	Lime	114			
31	Sand	145			
94	Sand	239			
65	Lime	304			
41	Lime	345			
79	Lime w/shale breaks	424			
10	Lime w/shale breaks	434			
80	Sandy shale	514			
44	Lime	558			
90	Shale	648			
36	Lime (40')	684			
36	Shale	720			
18	Lime (20')	738			
9	Shale & slate	747			
6	Lime (5')	753			
152	Shale & sndy shale	905			
72	Shale & sndy shale	977			
6	Core #1 -Full recovery - shaley sand	983			
2	Shale	985			
7	Good oil sand	992			
1	Light shale	993			
22	Sandy shale	1015			

Total Depth 1015'  
 Open Hole  
 Casing 7 at 21'.60  
 Casing 2" at 1012'  
 Casing at  
 Cement  
 Tubing  
 Rods  
 Additional Information  
 Ream & cut 20 ft. of pocket. Run 1012' of 2" tubing. Circulate hole clean.

Date completed April 19, 1963

O. K.

Started April 16, 1963

Superintendent