

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 33 T. 15 R. 26W E
 Loc. SW SW NE
 County Gove

API No. 15 —————
 County _____ Number _____

Operator _____
Donald C. Slawson

Address _____
408 120 Bldg. Wichita, Ks. 67202


Well No. 1 Lease Name Babcock 'E'

Footage Location _____
 feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Slawson Drlg. Co., Inc. Geologist George Mueller

Spud Date Dec. 18, 1975 Total Depth 4540 P.B.T.D. _____

Date Completed Dec. 31, 1975 Oil Purchaser N/A



Locate well correctly
 Elev.: Gr. 2570
 DF 2572 KB 2575

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		292	60/40 Poz	200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____	CFPB _____
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. 1 Lease Name Babcock 'E'

S 33 T 15 R 26 W E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			EL Tops	
Sand & Shale	0	298	ANH 2001 (+574)	
Shale & Shells	298	1555	HEEB 3835 (-1260)	
Sand, Shale & Shells	1555	2000	LANS 3874 (-1299)	
Anhydrite	2000	2039	STK 4118 (-1543)	
Shale & Lime	2039	2650	L/CK 4405 (-1830)	
L/KC Lime	2650	4000	MISS 4466 (-1891)	
Lime	4000	4540	LTD 4545 (-1970)	
RTD	4540			

DST #1 4052-4085 (160' zn), W-FB, 30-45-45-60,
Rec. 230' OGCM, IFP 55-74#, IBHP 1230#,
FFP 83-111#, FBHP 1221#

Drlg @ 4285'

DST #2 4463-4483 (Miss) 30-45-30-30,
Rec. 20' M w/SO, IFP 18-18#, IBHP 703#,
FFP 18-18#, FBHP 83#

DST #3 4483-4496 (Miss), 30-45-30-30,
Rec. 30' M, IFP 18-18#, IBHP 408#, FFP
18-18#, FBHP 213#

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Signature James C. Remsberg by Rene Stucky
Petroleum Engineer
Title _____

January 20, 1976
Date _____