


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- A. F. PARMELEE
Farm- Rousch No. 1

SEC. 19 T. 28 R. 17E
SE SE SE
220' N & W of Se corner

Total Depth. 974
Comm. 1-3-54 (?) Comp. 1-18-54
Shot or Treated.
Contractor.
Issued. 2-5-55

County Wilson
KANSAS



Elevation. _____

Production. dry

CASING:

10" 14'
8" 336'
7" 654'

Figures Indicate Bottom of Formations.

soil, clay	12	
lime	16	
shale	25	
sand water	70	
shale	125	
lime	215	
shale	250	
lime	275	
shale	285	
lime	330	SLM
shale	398	
lime	405	
shale	412	
lime	418	
shale	427	
lime	440	
shale	451	
lime	460	
shale	480	
sand	495	
Gas 48,000		
shale	536	
lime	540	
shale	543	
lime	570	
shale	608	
lime	628	
shale	630	
water & shale gas		
lime	638	
shale	642	
lime	645	
shale	654	SLM
shale	657	
sand	670	
Gas 32,000		
shale	722	
lime	724	
shale	730	
sand Oil Show	736	
shale light	775	
shale	912	SLM
sand	914	
sand Oil Showing		SLM
Core barrell at this		
point to	914-960	
(Sandy all the way.		
Core was take to oil		
field research lab.		
fortest ing		
The core did not have		
sufficient saturation		
to justify trying to		
make a well.)		
Sand finished drilling		
in sand	967	
and drilled 7'		
of black shale	974	
Total Depth		