

Company

Farm Ellen Randall

No. 3

20-28-17E
Sec. 20 T. 28 R. 17 E
Loc. SE $\frac{1}{4}$ SW $\frac{1}{4}$
County Wilson

Total Depth 930'


Comm. Dec. 8, 1941

Shot or Treated

Contractor Frank Young

Issued

Comp. Dec. 18, 1941



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

soil and clay	10	water at 14' 3 bbls. per hour
lime	15	
shale	80	
lime	90	little water, 1 bbl. per hour
shale	138	
lime	215	
shale	220	HFW
lime	225	
shale	255	
lime	260	
shale	270	
lime	280	
shale	285	
lime	334	
shale	368	
lime	370	
shale	400	
lime shells	430	little gas at 400
lime	450	
shale	535	
lime	573	
shale	608	
lime	628	
shale	636	water
lime	643	
shale	660	
sand	680	
shale	733	
lime	735	
shale	800	
sand	810	
shale	876	
gas, sand	893	
sand	912	
shale	930	TD

Shot from 893 to 911 with 93 quarts.