

21-16-23W

D R I L L E R S L O G

#1 Scherzinger "B"

CASING RECORD:
7 jts. new 20#
8-5/8" surface
casing

COMPANY: Palomino Petroleum
CONTRACTOR: Strata Drilling Company

DESCRIPTION: NW SE NE
Section 21-16S-23W
Ness County, Kansas

COMMENCED: November 10, 1979

ELEVATION: 2469' KB

TOTAL ROTARY
DEPTH: 4490'

COMPLETED: November 18, 1979

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	300	Ran 283' of new 20# 8-5/8" casing,
Shale, sand, shale	300	1808	set and cemented at 288' with 180
Anhydrite	1808	1845	sacks common cement, 2% gel, 3% C.C.
Shale and shells	1845	2480	Cement circulated. Plug down at
Lime and shale	2480	4442	10:15 p.m., November 10, 1979.
Lime	4442	4490	
			Ran 3 drill stem tests.
			Ran 1 electric log.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 925', 20 sacks @ 170', hulls and 10 sacks @ 40'. Job completed at 2:15 p.m., November 18, 1979.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I hereby certify that this is a true and correct copy of the above log
to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp