

Company Campbell & Horrell

Farm Friedline

No. 2

20-28-17E
 Sec. 20 T. 28 R. 17E
 Loc. NW of NE $\frac{1}{4}$
 County Wilson

Total Depth 962

Comm. 10-20-36

Comp. 11-18-36


Shot or Treated Shot 918-950 with 90 qts.

Contractor

Issued

Casing

20 in.	10 in
151/2	8 1/4 --414
121/2	6 5/8 --903
133/8	5 3/16



Elevation

Production

Figures Indicate Bottom of Formation

4	soil	4	19	shale	light	909--6 $\frac{1}{4}$ --903
6	clay	10	11	sand		920--gas
16	shale	26	30	sand		950--oil
69	shale	95--water 35'	12	shale		962--TD
16	shale	111				
10	shale	121				
6	lime	127				
43	shale	170				
78	lime	248				
5	shale	253				
9	lime	262				
18	shale	280				
14	lime	294				
9	shale	303				
3	lime	306				
10	shale	316				
43	lime	359				
55	shale B	414--8 $\frac{1}{4}$				
11	shale white	425				
15	sand	440				
10	shale	450				
5	lime	455				
13	shale	468				
32	lime	500				
15	shale	515				
20	sand	535				
35	shale sandy	570				
40	lime	610				
34	shale	644				
20	lime	664--20'				
4	shale	668				
5	lime	673				
10	shale dark	683				
4	shale white	687				
5	shale sandy	692				
5	sand hard	697				
50	shale sandy	755				
3	lime	758				
132	shale dark	890				

Shot 918-950 with 90 qts.