

Company Hoover & Taylor

Farm Reese

No. 9

Sec. 20 T. 28 R. 17 E

Loc. NW $\frac{1}{4}$

County Wilson

20-28-17E

Total Depth 932

Comm.

Comp. May 1940

Shot or Treated Shot 912-932---93 qts.

Contractor

Issued

Casing

20 in.

10 in

151/2


8 1/4 ---40'

12 1/2

6 5/8 ¹/₄ ---870

13 3/8

5 3/16



Elevation

Production

Figures Indicate Bottom of Formation

3	soil	3
10	clay	13
27	shale	40--8 $\frac{1}{4}$
10	lime	50
20	shale	70
5	lime	75
35	sand	110--water
55	shale	165
79	lime	244
6	shale B	250
5	lime	255
20	shale	275
10	lime	285
4	shale	289
10	lime	299
9	shale	308
42	lime	350
48	shale dark	398
37	shale	435
45	lime	480
5	shale dark	485
87	shale	572
36	lime	608
32	shale	640--SLM
18	lime	658
4	shale dark	662
5	lime	667
5	slate black	672
15	shale	687
10	sand	697
57	shale	754
2	lime	756
75	shale	831
10	sand	841
27	shale B	868
40	shale light	908--6 $\frac{1}{2}$ ---870'
4	gas sand	912
20	oil sand	932

shot 912-932---93 qts. 5-16-40