

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,

Wichita, Kansas


15-33-3E

Company- McNEISH & GRALAPP  
Farm- Bird No. 3

SEC. 15 T. 33 R. 3E  
NW NW SW

Total Depth. 3265'  
Comm. 4-17-58 Comp. 4-26-58  
Shot or Treated.  
Contractor. Watson Drilling Company  
Issued. 7-5-58

County Cowley  
KANSAS



CASING:

Elevation. 1155 RB

8 5/8" @ 143'  
5 1/2" @ 3279' w/75 sx. Casing set 5' off bottom. Production. 20 BOPD  
Figures indicate Bottom of Formations.

surface clay & lime	200
lime & shale	1600
lime	1660
shale & lime	2015
shale	2165
lime & shale	2310
shale & sdy lime	2440
shale	2619
sand & shale	2730
shale	2773
lime & shale	2858
lime	2895
sand & shale	2935
shale	2963
lime	3081
lime & shale	3210
shale	3224
sand & shale	3256
Mississippi lime	3262
Mississippi lime	3265
TOTAL DEPTH	

TOPS: (Scout)	
Layton	2625
Cattleman Sand	3168
Mississippi	3260

CABLE TOOL LOG

M. G. M. Drilling Company  
Winfield, Kansas.

Comm: 5-1-58  
Comp: 5-9-58

Acidized & fracked. Dumped 75 sacks  
cement. Well started flowing after  
being fracked.