


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas

Company- WRICO DRILLING CO., ET AL  
 Farm- Miller No. 2

SEC. 15 T. 33 R. 3E  
 NW SE NE

Total Depth. 3340'  
 Comm. 9-12-56 Comp. 9-24-56  
 Shot or Treated.  
 Contractor. Wrico Drilling Co.  
 Issued. 12-1-56

County Cowley  
 KANSAS



Elevation. 1164' Gr.

Production. 305 BOPD

CASING:

8 5/8" @100' w/80 sx cem.  
 5 1/2" @3340' w/75 sx cem.

Figures Indicate Bottom of Formations.

soil-subsoil	20
sand	40
shale	60
lime	100
shale	320
shale lime	926
shale shells	1260
lime shale	2248
Stalnaker sand	2274
sand lime	2374
lime shale	2570
shale	2640
shale Layton sand	2756
shale lime	2835
Kansas City lime shale	2895
lime shale	3024
lime	3082
lime shale	3193
sand shale	3216
shale, sandy	3271
Mississippian	3274
Core #1 3274-3293	
Mississippian	3339 K.B.
Mississippian	3340
Total Depth	

GEOLOGICAL TOPS	
Stalnaker Sand	2238
Layton sand	2638
Kansas City lime	2802
Oswego lime	2992
Cherokee, shale	3094
Skinner sand zone	3193
Mississippi Chert-	3271
Mississippi Lime	3313