

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

22-32-4E

CASING RECORD

LOCATION NW NE SE SW


SEC 22 T.32 R 4 E.

10"  
 20" 8 1-4  
 15 1-2 6 5-8  
 12 1-2 1100 5 3-16  
 TOTAL DEPTH  
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

FARM Madison  
 COMPANY W. M. McKnab  
 CONTRACTOR W. M. McKnab.  
 COMMENCED March 17, 1927.

NO. 1 COUNTY Cowley

COMPLETED April 16, 1927



SHOT QUARTS BETWEEN

ELEVATION

INITIAL PRODUCTION  $4\frac{1}{2}$  M. cu. ft gas.

FIGURES INDICATE BOTTOM OF FORMATIONS.  
 REMARKS

Formation	Depth	Formation	Depth
lime broken white	95	lime white hrd	1250
shale dark sft	100	(Little water 1250')	
red rock red sft	105	shale dark sft	1270
shale blue sft	165	lime white hrd	1295
lime white hrd	185	shale lgt sft	1310
shale blue sft	195	lime white hrd	1315
red rock red sft	205	shale drk sft	1330
lime white hrd	210	lime white hrd	1370
lime white hrd	215	shale drk sft	1377
shale blue sft	260	lime white hrd	1380
lime white hrd	275	shale lgt sft 2 BW 1415'	1410
lime white hrd	285	sand gray sft	1420
shale drk sft	310	shale drk sft	1440
		lime white hrd	1442
shale drk sft	325	shale drk sft 8 BW 1460'	1458
red mud red sft	350	sand gray sft	1470
shale drk sft	360	lime white hrd	1480
lime white hrd	375	shale drk sft	1492
shale white sft	395	lime white hrd	1538
(15 1/2" pipe set 395')		shale drk sft	1560
lime white hrd	408	lime white hrd	1567
shelly lime white hrd	435	shale drk sft	1575
shale blue sft	445	lime white hrd	1578
lime white hrd	450	shale drk sft Cave	1612
shale drk sft	460	(Set 10" pipe at 1610')	
lime white hrd	475	red rock red sft	1613
shale white sft	485	shale light sft	1632
lime white hrd	490	lime white hrd	1646
shale drk sft	505	shale white sft	1650
(Little water 550')		lime white hrd	1657
lime shelly gray sft	570	shale drk sft	1662
shale light sft	595	shale white sft	1670
lime white hrd	600	lime white hrd	1672
shale drk sft	670	shale white sft	1695
lime white hrd	680	(Cave rimmed 10" pipe to 1695')	
shale drk sft	700	lime gray broken	1707
lime white hrd	715	shale white sft	1730
sandy shale drk sft	775	lime white hrd	1735
lime white hrd	780	sandy shale gray sft	1750
shale drk sft	865	lime sandy gray hrd	1755
lime white hrd	895	sandy shale gray sft	1800
shale sandy drk sft	920	(1 1/2 BW 1800')	
lime white hrd	930	sand gray sft	1820
shale drk sft	940	shale drk sft	1835
lime white hrd	950	lime white hrd	1839
shale drk sft	965	sandy shale white sft	1870
lime white hrd	975	sand white sft HFW 1870'	1890
shale drk sft	1015	sandy lime white hrd	1910
lime white hrd	1022	sand sharp white sft	1990
shale drk sft	1060	sandy lime white hrd	2005
lime white hrd	1064	shale drk sft	2008
shale drk sft	1070	lime white hrd	2035
shale white hrd	1080	shale drk sft	2060
(6 BW 1085')		lime white hrd	2063
shale drk sft	1087	sandy shale drk sft	2085
lime white hrd	1090	lime white hrd	2086
shale drk sft	1102	sand gray sft	2108
lime white hrd	1120	(Set 8 1/2" csg. at 2110')	
shale dark sandy sft	1175	shale drk sandy	2274
lime white hrd	1200	gas sand gray sft	2302
shale drk sft	1205	gas from 2280 to 2297'	
lime white hrd	1210	Test 4 1/2 M.	
shale drk sft	1214	Set 6 5/8" csg. 2274'.	