

Company- K. T. WEIDEMANN OIL CO.
Farm- Elam-Stayton No. 5

SEC. 31 T. 32 R. 4E
SE NE NE

31-32-4E

Total Depth. 3160 $\frac{1}{2}$

Comm. 7-6-51


Comp. 7-23-51

Shot or Treated.

Contractor.

Issued. 9-13-52

County Cowley
KANSAS



Casing:

8 5/8" 122' com. w/95 sx
5 1/2" 3122' com. w/45 sx

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

cellar	5
clay	20
lime & shale	205
lime	457
red rock	477
lime & shale brks	650
shale & shells	920
sand	945
sandy shale	1010
lime	1050
shale & shells	1370
lime & shale	1665
lime	1742
shale	1895
lime & shale brks	1950
shale	2025
shale & lime	2030
shale	2115
lime & shale brks	2160
lime	2175
lime & shale	2340
shale	2540
sandy shale	2565
shale & shells	2595
shale	2658
lime	2769
shale	2785
lime & shale	2885
lime	2955
lime & shale	3010
shale	3119
sandy	3122 RTD
sand	3160
lime	3160 $\frac{1}{2}$
Total Depth	

Tops:

Layton Sandstone	2490
Kansas City 1st.	2658
Base-Kansas City 1st	2769
Cherokee Shale	2955
Bartlesville	3119
Miss. Lime	3160

Rotary table to ground
level 3.5'

2955
1164
1791