

Company - K. T. WIEDEMAN
Farm - John V. Elam -
George D. Stayton

No. 1


SEC. 32 T. 32 R. 4E
SW SW NW

Total Depth. 3138
Comm. 5-2-49
Shot or Treated. 40 qts.
Contractor.
Issued. 12-17-49

Comp. 6-14-49

County. Cowley

KANSAS



Elevation. 1172 feet

Production. 12 Bbls.

CASING:

8" set @ 120' w/50 sx.
5" set @ 3122' w/38 sx.

Figures Indicate Bottom of Formations.

Cellar	5
Shale	20
Lime	65
Shale	87
Lime	90
Shale	98
Lime	100
Broken lime	140
Shale	150
Lime	159
Shale	200
Lime	232
Red rock	235
Lime	317
Shale	331
Lime	350
Lime shale breaks	445
Shale	525
Lime	550
Shale	801
Lime	812
Shale	944
Sandy shale	1007
Shale	1026
Lime	1045
Shale shells	1240
Shale	1260
Lime	1300
Shale lime streaks	1400
Shale	1425
Lime shale breaks	1500
Shale shells	1540
Lime	1580
Shale	1670
Lime	1745
Shale	1825
Lime	1840
Shale	1865
Shale shells	1985
Shale lime streaks	2080
Shale lime shells	2108
Sandy shale	2120
Shale	2170
Lime	2175
Shale	2310
Shale shells	2420
Shale	2525
Sand	2570
Shale	2680

Lime	2785
Shale shells	2835
Lime	2910
Lime-shale	2960
Shale	2975
Shale lime	3090
Shale	3115
Sand	3116
Shale & sand	3126
Sand cored	3138
Rotary Total Depth	
Cable tools	
Drld. out cement-cleaned	
out mud	3138 TD

Overnight fillup taken at
8:30 A.M. 6-15-49 465'
At 1:00 P.M. 615'
Fluid level 11:00 A.M. 616'
940' - plenty of gas

FORMATION TOPS

Stalnacher sand	2108
Layton sand	2490
Base Layton sand	2578
Top Kansas City lime	2665
Base Kansas City	2760
Top Cherokee shale	2960
Bartlesville sand	3114

2715
1173
-1131
131