

31-28-17E
Wilson Co.

Jerry L. Phillips

Oil and Industrial Supply

OFFICE AND YARDS
1212
1092 NORTH SANTA FE
P. O. BOX 350
TELEPHONE
316-431-3489

Chanute, Kansas 66720 February 28, 1975

Jones & Campbell
c/o Mr. W. H. Campbell
4121 W. 83rd
Prairie Village, KS 66201

- ♦ OILFIELD RENTAL EQUIPMENT
- ♦ PLASTIC PIPE AND FITTINGS
- ♦ DEALERS IN ABANDONED LEASES
- ♦ PLUMBING SUPPLIES
- ♦ GAS AND OIL WELL SUPPLIES
- ♦ USED TANKS AND PIPE

JLP Drilling Report

Date: Feb. 13, 1975
Lease: Short OE3
Well Size: 4 3/4"
Surface Pipe: 5 1/2" - set 10'

Driller: Ed McKinsey
County: Wilson
Rig: #3

0 - 1	Soil	1 ft.
1 - 2	Broken Lime 8	1
2 - 5	Clay	3
5 - 137	Shale w/Lime Brks	132
137 - 180	Water Sand	43
180 - 232	Shale w/Lime Brks	52
232 - 262	Lime (Kansas City)	20

Date: Feb. 14, 1975

262 - 343	Lime	81
343 - 353	Shale	10
353 - 428	Lime	75

Trip out at 303 ft. for new bit.

Date: Feb. 17, 1975

428 - 450	Lime	22
450 - 453	Gray Shale	3
453 - 458	Black Shale w/Brks	5
458 - 500	Shale w/Brks	42
500 - 510	Lime	10
510 - 530	Shale w/Brks	20
530 - 547	Lime	17
547 - 563	Shale w/Bkrs	16

Trip at 523 ft. for new bit.

Date: Feb. 18, 1975

563 - 645	Shale w/Brks	82
645 - 652	Lime (Light Gray)	7
652 - 675	Lime	23
675 - 718	Shale	43

31-28-17E

Jerry L. Phillips

Oil and Industrial Supply

OFFICE AND YARDS
1372
4002 NORTH SANTA FE
P. O. BOX 350
TELEPHONE
316-431-3489

Chanute, Kansas 66720 February 28, 1975

Jones & Campbell

page 2

- ♦ OILFIELD RENTAL EQUIPMENT
- ♦ PLASTIC PIPE AND FITTINGS
- ♦ DEALERS IN ABANDONED LEASES
- ♦ PLUMBING SUPPLIES
- ♦ GAS AND OIL WELL SUPPLIES
- ♦ USED TANKS AND PIPE

718 - 738	Lime	20 ft.
738 - 747	Shale	9
747 - 753	Lime	6
753 - 756	Shale	3
756 - 757	Coal	1
757 - 759	Shale	2
759 - 761	Lime	2
761 - 769	Shale	8
769 - 770	Lime Cap Rock	1
770 - 771	Oil Sand	1

Trip out for Core Barrel.

Date: Feb. 19, 1975

771 - 791	Core #1 - Good Oil Sand	20
791 - 811	Pocket	20

Date: Feb. 20, 1975

Run 2" tubing.