


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - WESTGATE GREENLAND OIL CO.
Farm - Miller No. 5

SEC. 3 T. 12 R. 17W
NE SW NE

Total Depth. 4054 ✓
Comm. 10-13-49 Comp. 10-29-49
Shot or Treated.
Contractor. Jackson Drlg. Corp.
Issued. 1-21-50

County. Ellis
KANSAS



Elevation. 2049 ft.

Production. S.W.D.W.

CASING:

9 5/8" 190' cem w/125 sx.
5 1/2" 3732' cem w/250 sx.

Figures Indicate Bottom of Formations.

sand, clay	30
shale	190
shale, shells	475
sand	490
shale, shells	580
Dakota sand	680
shale, shells	805
sand	905
red bed, shale	1260
anhydrite	1295
shale, shells, salt	1835
lime, shale	3310
lime	3540
conglomerate	3565
lime, shale	3665
conglomerate	3720
conglomerate, lime	3770
lime	4035
gravel wash	4052
gravel	4054
Total depth	

Tops:	
Heebner	3234
Lansing	3278
Conglomerate	3540
Simpson	3575
Arbuckle	3650

Measurements from top of derrick floor.
Perforated casing at 2662' cem w/800 sx.

Ran Halliburton temperature survey - perf. casing
w/2 shots at 1674'. cem w/600 sx.