

Gift of
W. L. Stryker Estate
State Geological Survey of Kansas
1970
Farm *Short*

WELLORECORD

Well No. *1* Producer *C. Buddrum*
 Location *660 from East line 330 from North line* Sec. *31* Twp. *28 S* Rg. *17 E*
 Elevation, State *Kans* County *Wilson*
 Kind (Oil, Gas, Water, Dry Hole) *oil* Contractor *Boyd W. Bogle*
 Producing formation *Squirrel sand* Top *680* Bottom *686*
 Shot with _____ qts. _____ from _____ to _____
 Packer Set at *4" sub 682* Kind _____ Size *6 7/8*
 Liner _____ from _____ to _____ Perforated from _____ to *6 7/8*
6 20
60

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
0	<i>Sub P clay</i>	15	34	<i>lime</i>	585
5	<i>fine sand</i>	20	21	<i>shale gas</i>	606
2	<i>lime</i>	22	8	<i>sand</i>	614
4	<i>shale</i>	26	14	<i>shale</i>	628
2	<i>sand rock</i>	28	20	<i>lime 20 feet</i>	648
2	<i>shale</i>	30	5	<i>shale</i>	653
6	<i>lime</i>	36	5	<i>lime 5 feet</i>	658
20	<i>D shale</i>	56	4	<i>B slate</i>	662
14	<i>lime</i>	70	16	<i>shale</i>	678
28	<i>sand</i>	98	16	<i>oil sand</i>	694
1	<i>coal</i>	99		<i>shale</i>	
16	<i>D shale</i>	115			
1	<i>lime</i>	116			<i>694 T.D.</i>
46	<i>shale</i>	152			
103	<i>limes</i>	255			
3	<i>slate</i>	258			
2	<i>lime</i>	260			
5	<i>l. shale</i>	265			
22	<i>lime</i>	287			
11	<i>shale</i>	298	✓		
57	<i>lime</i>	355			
59	<i>shale</i>	414			
9	<i>lime</i>	423			
5	<i>shale</i>	428			
9	<i>lime</i>	437			
3	<i>shale</i>	440			
19	<i>lime</i>	459			
44	<i>shale</i>	503			
27	<i>sand</i>	530			
21	<i>shale</i>	551			

Total Depth

Open Hole

Casing *10"* at *18*
 Casing *8"* at *360*
 Casing *7"* at *675*
 Cement *15 sacks req*
 Tubing *685-7 19 feet of anchor*
 Rods *683-4 8 foot polished rod*
 Additional Information *2-6 foot sub 1-8 foot sub*

Hole filled with water *14*
 more water *22 feet*
 Hole full at *662*

fractured with *4000 lbs*
2000 lbs 2000 @ same
 used *100 Bbl oil*
 run acid to Breakdown
 Break at *1750* took sand
 at *1700* shut in at *500*
 flowed back *60 bbls*
 Hole drilled to *704* for
 pocket, under sand

Date Completed *Aug 9 57*

O. K.

Superintendent

004