


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- STELBAR OIL CORP. INC.  
Farm- Tower No. 1

SEC. 36 T. 30 R. 3E  
SE NE SW

Total Depth. 3353'  
Comm. 1-13-57 Comp. 1-2-57  
Shot or Treated.  
Contractor. Prairie Oil & Gas Co., Inc.  
Issued. 3-9-57

County Cowley  
KANSAS



CASING:  
8 5/8" 121' w/100 sx cem.

Elevation. 1225' DF

Production. Dry

Figures indicate Bottom of Formations.

clay	15
brkn lime	510
shale-shells	1525
lime	1605
shale	1805
sand-shale	2150
shale	2235
sand	2260
shale	2421
Kansas City lime	2547
lime	2678
shale-lime	2941
Bartlesville sand-cored	2950
shale-cored	2971
shale	3008
Mississippi lime	3272
shale	3350
Arbuckle lime	3353 RTD
Total Depth	

TOPS:

Kansas City	2421
B/Kansas City	2696
Cherokee	2846
Bartlesville	2941
Mississippi	3008
Kinderhook	3228
Arbuckle	3350

DST #1 3347-3353 Open 1 hr.,  
good blow. Rec. 1947' sulphur  
wtr. 30 min. IBHP 1295#. 30 min.  
FBHP 1295#. I.F.P. 0#. F.F.P. 860#.