


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. AYLWARD & WILLIS BROS.
Farm. Soden No. 2

SEC. 19 T. 28 R. 17E
N. NW NW

Total Depth. 846'
Comm. 2-3-43 Comp. 2-14-43
Shot or Treated.
Contractor.
Issued. 5-21-49

County. Wilson



Elevation. _____

Production. 466,000 gas

CASING:
8 1/4" 13 1/2' Pulled
6-5/8" 404' Pulled
4-7/8" 715' Pulled

Figures Indicate Bottom of Formations.

soil	3
clay	10
shale	50
lime sdy	77
lime hrd	95
shale	100
sand wtr	203
shale	210
lime	287
shale blk	293
shale sdy	325
lime	351
shale	357
lime	402
shale	428
lime shells	485
lime	490
shale	500
lime hrd	514
shale	520
gas sand	535
shale	550
oil sand	558
shale	568
shale sdy	602
lime	638
shale	675
lime	695
slate blk	700
lime	707
lime & slate	714
shale	720
sand	730
shale	790
shale sdy	822
gas sand	846
Total Depth	

Tubed w/2nd hand 2" tubing
Packer set at 820'
Pin-Hole under packer
Gage at 842' - 844'
24' of 2" anchor
All casing pulled & hole
mudded to top.
Volume test 46,000 cu. ft
rock pressure 55 lbs.