

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS - PHONE HE1-2650

700 NORTH MISSION - OKMULGEE, OKLAHOMA - PHONE SK6-4444

Chanute, Kansas

September 18, 1965

K-K Drilling Company
P.O. Box 556
Chanute, Kansas

Gentlemen:

Attached hereto are the results of tests run on the Lower Bartlesville Rotary core taken from the Daley Lease, Well No. 6, located in the N $\frac{1}{2}$ SE $\frac{1}{4}$ of Section 19, T-28S, R-17E, Neosho County, Kansas, and submitted to our laboratory on September 13, 1965.

This core was sampled and the samples sealed in plastic bags by a representative of Oilfield Research Laboratories.

Your business is greatly appreciated.


Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

BRP:rf

5 c.



-LOG-Company K-K Drilling Company Lease Daley Well No. 6

Depth Interval, Feet	Description
-------------------------	-------------

829.0 - 831.0	Sandy shale.
---------------	--------------

831.0 - 832.0	Brown, laminated, shaly sandstone.
---------------	------------------------------------

832.0 - 835.0	Laminated sandstone and shale.
---------------	--------------------------------

835.0 - 836.0	Brown, laminated, shaly sandstone.
---------------	------------------------------------

836.0 - 857.5	Grayish brown, slightly shaly sandstone.
---------------	--

857.5 - 859.0	Gray shaly sandstone.
---------------	-----------------------

859.0 - 860.0	Shale.
---------------	--------

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company K-K Drilling Company Lease Daley Well No. 6

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1	831.1	14.3	22	45	67	244	2.2				
2	836.1	21.4	25	49	74	414	106.				
3	837.1	18.9	22	44	66	322	88.				
4	841.1	16.6	19	54	73	244	12.				
5	844.1	20.3	17	61	78	268	101.				
6	847.1	18.6	14	57	71	202	41.				