


Company- DRILLERS PRODUCTION COMPANY
 Farm- A. C. Aumann No. 2

SEC. 33 T. 33 R. 3E
 NW NE NE

Total Depth. 3363
 Comm. 12-15-52 Comp. 12-25-52
 Shot or Treated.
 Contractor. Springer & Harper
 Issued. 1-10-53

County Cowley KANSAS



CASING:
 8 5/8" 92' cem. w/100 sx

Elevation. 1139 RB.

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	48
lime	110
lime & shale	155
lime	205
shale & lime	340
lime	405
shale	435
lime & shale	595
red bed	620
lime & red rock	695
lime & shale	860
lime	900
lime & shale	1145
lime	1170
lime & shale	1290
shale & shells	1380
shale & lime	1480
shale	1530
lime	1705
lime & shale	1840
shale & shells	1885
lime	1900
shale	1965
lime	2045
shale	2115
sandy shale	2325
shale & lime	2450
shale	2650
sand & sandy shale	2718
layton sand	2807
shale	2837
lime	3165
shale & lime	3321
shale	3332
lime	3363
Total Depth	

Tops:	
Lansing	2202
Layton	2642
Kansas City	2826
Base-Kansas City	2945
Marmaton	3024
Cherokee	3147
Bart. Sand	3343-45 S.O.
Miss.	3348 S.S.O.

Cored 3321-48 1/2'