


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY 2-32-5E ✓
 412 Union National Bk. Bldg., Wichita, Kansas

Company - E. H. ADAIR OIL COMPANY
 Farm - Ewors No. 1

SEC. 2 T. 32 R. 5E
 SEc NE

Total Depth. 3133'
 Comm. 10-1-47 Comp. 10-11-47
 Shot or Treated.
 Contractor.
 Issued. 11-1-47

County. Cowloy
 KANSAS



8 1/4" CASING:
 125' Com. w/60 sx

Elevation. 1359 feet

Production. Dry

Figures indicate Bottom of Formations.

surface	5
shale	65
lime	325
shale & shells	1660
lime	1700
shale	1712
lime	1760
shale	1900
lime	1940
sand	2005
shale	2405
lime sdy	2447
lime	2835
shale	2990
shale sdy	3083
chat Miss.	3133
Total Depth	

Top of Bartlesville Zone 3011
 Trace sand mostly
 muddy blue shale 3011-19
 shale red 3026-29
 no Bartlesville sand
 Top Miss. Chat 3083
 No show oil in Miss. Limo