

3-32-5E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CYMCO PETROLEUM COMPANY  
Farm- Elrod No. 1

SEC. 3 T. 32 R. 5E  
W/2 W/2 NW

County Cowley KANSAS

Total Depth. 2425'  
Comm. 7-25-58 Comp. 7-31-58  
Shot or Treated.  
Contractor. Gearhart-Canaday Drlg. Co.  
Issued. 11-8-58



Elevation. 1302 DF

Production. 25 BOPD

CASING:

- 8 5/8" 194' w/135 sx. cem.
- 4 1/2" 2424' w/75 sx. cem.

Figures Indicate Bottom of Formations.

surface soil	2
○ lime	95
shale	130
lime & black shale	165
hard lime	175
lime	345
lime w/black shale	485
red beds	510
lime	600
shale	660
shale and shells	1000
shale	1275
shale and lime	1565
lime - shale	1716
shale and lime	1985
sand and sandy shale	2020
sand	2055
shale	2200
○ sand and shale	2250
shale	2374
sand	2375
limey sand	2377
sand show free oil	2382
○ shaley sand	2384
sand	2393
sand and shale	2405
sandy shale	2425 RTD
Total Depth	

GEOLOGICAL TOPS:

Stalnaker	1984
Layten	2373

Core # 1 2376-96

DST #1 2377-97 open 1 1/2 hours  
Good blow throughout Recovered 30'  
VHO & GCM 150'  
Sl: Watery oil & Gas cut Mud 568#/45 mins.

Core #2 2398 - 2415