

# WELL RECORD

3-28-18E<sup>pl</sup>

WELL No.: B 14 FARM; Sherman OPERATOR; Kanalta  
 LOCATION; 3 - 28S - 18E  
 ELEVATION: \_\_\_\_\_ STATE: Kansas COUNTY: Neosho  
 DRILLING CONTRACTOR: Circle W Drilling Inc RIG #: 1  
 PRODUCTION FORMATION: \_\_\_\_\_ TOP: \_\_\_\_\_ BOTTOM: \_\_\_\_\_  
 PERFORATED: \_\_\_\_\_

TOTAL DEPTH: 950' HOLE SIZE: 6 1/4"

CASING DETAILS: 53' of 7" surface casing

PUMP EQUIPMENT: \_\_\_\_\_

RODS & PUMP: \_\_\_\_\_

Thick ness	FORMATION	Depth	Thick ness	FORMATION	Depth
12'	Soil	12'	24'	Lime	593'
2'	Clay	14'	4'	Shale	597'
9'	River Gravel	23'	4'	Lime	601'
60'	Lime	83'	114'	Shale & Coal	715'
2'	Shale & broken Lime	85'	24'	Shale & broken Lime	739'
12'	Lime	77'	17'	Lime	756'
18'	Shale with breaks	95'	18'	Shale & Coal	774'
29'	Hard Lime	124'	13'	Lime	787'
7'	Shale	131'	7'	Shale gray	794'
59'	Shale & broken Lime	190'	12'	Shale gray & Coal	806'
97'	Lime & Shale	287'	19'	Shale & Lime (cored)	825'
89'	Shale	376'	31'	Shale (Sandy) & Clay	856'
33'	Shale & broken Lime	409'	71'	Sandy Shale & Lime	937'
4'	Lime	413'	12'	Lime & Clay	939'
30'	Shale	443'	11'	Coal & Shale	950'
2'	Lime	445'			
7'	Shale	452'			
3'	Lime	455'			
31'	Shale	486'			
5'	Lime	491'			
3'	Shale	494'			
37'	Lime	531'			
24'	Shale	555'			
3'	Lime	558'			
11'	Shale & Coal	569'			