


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ROOKS & HALL
Farm - Wise "B" No. 1

SEC. 1 T. 33 R. 4 E
SE NE NW

Total Depth. 3138'
Comm. 5-27-45 Comp. 7-12-45
Shot or Treated. Shot 7' 3135-27' 500 gals. acid
Contractor. C. L. Brosius Drlg. Co.
Issued. 10-6-45

County. Cowley
KANSAS



CASING:

15"	490'	8 1/4"	2129'
12 1/2"	1125'	6 5/8"	2528'
10"	1542'	5"	3128

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	shale	990	sand	1975
shale (wtr-3 B @ 20')	15	red rock	995	shale	2000
lime brkn	50	shale	1020	sand	2080
lime	105	lime hrd	1030	shale	2125
shale lgt	110	shale	1070	lime	2140
red rock	125	lime	1085	shale	2160
shale blue	160	wtr sand 4 BW	1090	lime sdy	2175
lime	200	lime	1105	shale	2215
shale	205	shale	1122	shale blk	2240
red rock	215	lime	1140	shale	2325
lime	225	shale	1150	shale & shell	2345
shale blue	230	lime	1170	shale lgt	2365
lime	285	shale	1180	sand	2380
shale	290	lime	1190	(oil & wtr 2365-70')	
lime	300	shale	1225	lime	2455
shale	305	lime	1235	shale	2540
lime	335	shale	1237	lime	2610
red rock	355	lime	1275	shale blk	2625
shale brwn	370	shale	1285	lime	2630
red rock	390	lime	13 25	lime sdy	2638
shale	400	shale	1330	(Corr. Meas. 2628')	
lime	415	lime	1335	lime	2715
shale	420	shale	1345	(show of oil 2690')	
lime	425	lime	1365	shale	2730
shale	435	shale	1370	lime	2775
lime	440	lime	1415	shale blk	2780
shale	455	shale	1420	lime	2855
lime	465	lime	1430	(show of oil 2830')	
shale	475	shale	1465	shale	2915
lime	490	lime	1470	lime sdy	2925
shale	505	shale lgt	1485	shale sdy	2976
lime	515	red rock	1492	sand	2986
shale	520	lime	1505	shale	2992
lime	525	sand HFW	1520	shale sdy	3010
shale	530	shale	1540	shale	3017
lime	545	lime	1542	red rock	3018
shale	550	shale & shell	1590	shale sdy	3022
lime	555	shale	1615	sand	3050
shale	600	lime	1622	shale blk	3070
lime (gas 625-35')	620	shale blk	1630	red rock	3090
shale	635	lime	1635	cherty lime	3135
lime	650	shale	1645	(show oil 3115')	
shale	660	red rock	1685	(more oil ' gas 3135'	
lime	670	shale	1690	wtr)	
shale blue	675	lime	1715	lime sdy (wtr inc.)	3138
lime	685	shale	1725	Total Depth	
shale	700	lime	1730		
lime	705	shale	1735		
shale	790	lime	1745		
lime	800	sand (show of oil) Hoover	1750		
shale	875	shale wh	1760		
lime	885	shale brwn	1773		
shale	890	lime	1780		
lime	900	shale	1812		
shale	925	lime sdy	1816		
lime	950	shale	1915		
shale	955	lime	1918		
lime	970	sand HFW	1920		
		shale	1970		

2855
1205
1650
10' oil
29 1 24