

COPY

DRILLING LOG

OPERATOR: OIL LAND, INC.  
 1725 S.W. 3rd  
 Topeka, Kansas 66606

COUNTY: JEFFERSON

TOTAL DEPTH: 1864'

Sec. 7 Twp. 10 Rge. 17

LEASE: WHITE

WELL: #1

FIELD:

THICKNESS	FORMATION	DEPTH
2	SOIL	2
11	CLAY - Yellow	13
2	LIME	15
43	SHALE	58
13	LIME	71
5	SHALE	76
9	LIME	85
44	SHALE	129
21	LIME	150
6	SHALE	156
3	LIME	159
66	SHALE	225
25	LIME	250
40	SHALE	290
2	LIME	292
40	SHALE	332
4	LIME	336
32	SHALE	368
2	LIME	370
13	SHALE	383
6	LIME	389
21	SHALE	410
1	LIME	411
16	SHALE	427
2	COAL	429
83	SHALE - Sandy	512
3	LIME	515
11	SHALE	526
6	SHALE - Red	532
100	SHALE	632
6	LIME	638
8	SHALE	646
17	LIME	663
6	SHALE	669
5	LIME	674
16	SHALE	690
22	LIME	712
24	SHALE	736
8	LIME	744
10	SHALE	754

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 24 1991

REGISTRATION DIVISION  
 Topeka, Kansas

7-10-17E

Oil Land, Inc.

CO

WHITE LEASE

WELL #1

THICKNESS	FORMATION	DEPTH
6	LIME	760
17	SHALE	777
15	LIME	792
2	COAL	794
4	SHALE	798
10	LIME	808
3	COAL	811
5	LIME	816
12	SHALE	828
12	LIME	840
8	SHALE	848
21	LIME	869
7	SHALE	876
44	LIME	920
10	SHALE	930
23	LIME	953
2	SHALE	955
3	LIME	958
5	SHALE	963
12	LIME	975
2	SHALE	977
3	LIME - LANSING	980
128	SHALE	1108
9	LIME	1117
3	SHALE	1120
5	LIME	1125
9	SHALE	1134
11	LIME	1145
5	SHALE	1150
2	LIME	1152
5	SHALE	1157
2	LIME	1159
10	SHALE	1169
5	LIME - BASE KANSAS CITY	1174
84	SHALE	1258
9	LIME	1267
5	SHALE	1272
7	LIME	1279
20	SHALE	1299
4	LIME	1303

RECEIVED  
STATE CORPORATION COMMISSION

SEP 24 1991

CONSERVATION DIVISION  
Wichita Kansas

7-10-17E

OIL LAND, INC.

WHITE LEASE

WELL #1

THICKNESS	FORMATION	DEPTH
30	SHALE - Broken	1333
5	LIME	1338
72	SHALE	1410
2	COAL	1412
86	SHALE	1498
2	LIME	1500
10	SHALE	1510
2	COAL	1512
4	SHALE	1516
2	COAL	1518
78	SHALE	1596
11	SAND - Large Clear	1607
3	SHALE	1610
21	SAND - Large Round Clear	1631
8	SHALE - Sandy - Broken	1639
45	SAND	1684
8	SHALE	1692
54	SAND - Large Clear	1746
61	SHALE	1807
3	LIME	1810
11	SHALE	1821
1	COAL	1822
42	LIME - Mississippi Lime	1864 T.D.

Well Plugged by Consolidated

15 Sacks 1860'  
 15 Sacks 1160'  
67 Sacks 350' to Surface  
 97 Sacks Total

RECEIVED  
STATE OIL AND GASES COMMISSION

SEP 24 1991

SECTION  
LAW OFFICES