


MCLAUGHLIN ET AL.  
Bankers Life No. 1.

SEC. 3 T. 10 R. 20 E.  
CNL SW SW

Total Depth. 1491  
Comm. 1-26-42 Comp. 2-26-42  
Shot or Treated.  
Contractor. Wilson.  
Issued. 5-2-42

County Leavenworth.



CASING.

10" 26'  
8 1/4" 960'  
65/8" 1450'

Elevation. 1104 Hawth

Production. 60 B.

Figures Indicate Bottom of Formations.

soil	2	shale	625	shale dark	1315
clay	23	lime	635	shale light sdy	1325
lime shells	28	shale	650	sand	1340
shale dark	29	lime	659	shale dark	1345
lime	32	shale	674	sand	1353
shale	42	lime	677	shale sdy	1370
lime	48	shale	685	shale dark	1390
shale sdy	65	lime	687	shale blk	1405
shale	73	shale	697	shale sdy	1410
shale	77	lime	715	shale dark	1439
lime	80	lime	724	shale light	1445
shale	100	shale dark	731	shale dark	1455
shale	108	lime	750	sand Oil	1491
lime	120	break blk	753		
shale	123	lime	759	Total Depth.	
lime	140	shale	763		
shale	147	lime	771		
lime	149	shale	780		
shale dark	155	shale dark sdy	785		
shale	160	sand	795		
lime	166	shale dark	803		
shale	264	lime sdy	808		
shale	302	sand	815		
shale red	305	shale	824		
shale light sdy	330	shale	895		
sand 5 BWPH	334	lime shelly	905		
lime	337	shale	917		
sand	360 <sup>23</sup>	lime	922		
shale sdy	365 <sup>5</sup>	shale	925		
shale	392 <sup>27</sup>	lime	929		
sand	396 <sup>4</sup>	shale	935		
shale	432 <sup>30</sup>	lime	950		
shale	442 <sup>20</sup>	shale	958		
lime	447 <sup>5</sup>	No log	962		
shale	451 <sup>4</sup>	lime	965		
lime	465 <sup>14</sup>	shale	970		
shale dark	469	No log	975		
lime	475	lime	982		
shale grey	485	shale	1000		
shale sdy	490	lime	1005		
lime	508	shale dark	1018		
shale	510	sand	1028		
shale red	513	shale sdy light	1049		
shale	525	shale	1125		
shale	541	shale light sdy	1140		
lime	549	shale dark	1147		
shale and lime	554	shale	1202		
shale grey	562	shale	1235		
shale	575	sand	1248		
lime	594	water @ 1235			
shale	605	shale	1260		
shale	608	shale	1291		
lime	616	shale light	1300		