

7-33-4E


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- WRICO DRILG. CO., ET AL  
Farm- Carl Whitson No. 1

SEC. 7 T. 33 R. 4E  
NW NW SW

Total Depth. 3285'  
Comm. 11-25-57 Comp. 12-3-57  
Shot or Treated.  
Contractor. Wrico Drilg. Co.  
Issued. 4-12-58

County Cowley  
KANSAS



Elevation. 1180' DF

Production. 25 BOPD

CASING:

8 5/8" 109' w/80 sx cem.  
5 1/2" 3285' w/150 sx. cem.

Figures indicate Bottom of Formations.

soil, clay, sand	70
shale, lime	1975
shale	2120
Stalnaker sand	2248
shale	3385
shale, lime	2564
Layton sand	2584
sand, shale	2596
sand, shale, lime	2740
Kansas City lime	2818
lime, shale	2902
lime	3000
lime, shale	3210
shale	3232
Mississippi chert	3260
Mississippi lime	3285
Rotary Total Depth	

TOPS:

Stalnaker sand	2122
Layton	2564
Kansas City lime	2738
Oswego lime	2918
Cherokee shale	3036
Mississippi chert	3231
Mississippi lime	3259