

MID-CONTINENT PETROLEUM CORPORATION

William Letsch, Well #6

990' from South & 330' from East lines of NW $\frac{1}{4}$  Sec 26-14S-13W, Russell County, Kansas

Drilling Contractor: Mac & Stauffer

Commenced: 3-22-39; Completed: 4-26-39. Initial Production: 1411 Bbls.

Soil	0	4
Clay	4	30
Clay & Shells	30	60
Clay	60	152
Sand Rock	152	178
Lime	178	236
Shale & Shells	236	325
Clay & Shells	325	410
Red Rock & Shells	410	650
Anhydrite	650	690
Shale	690	767
Shale & Shells	767	909
Anhydrite	909	934
Shale, Shells & Salt	934	1150
Salt & Shells	1150	1300
Shale & Shells	1300	1445
Lime Broken	1445	1551
Shale & Lime	1551	1660
Lime Broken	1660	1725
Shale & Shells	1725	1754
Lime Broken	1754	1862
Lime & Shale	1862	1966
Lime Broken	1966	2155
Shale & Lime	2155	2277
Lime, Shells & Shale	2277	2345
Lime Broken	2345	2445
Shale & Shells	2445	2505
Lime	2505	2532
Shale	2532	2548
Lime	2548	2570
Lime, Topeka	2570	2650
Lime Broken	2650	2654
Lime	2654	2835
Shale	2835	2842
Shale	2842	2857
Lime K.C.	2857	2867
Shale Black	2867	2869
Shale Red	2869	2872
Shale Green	2872	2873
Lime Broken	2873	2874
Lime K.C.	2874	2876
Lime K.C.	2876	2887
Lime K. C.	2887	2890
Lime K.C.	2890	

CASING RECORD

13" OD 40# New L.W. Csg. 193'5" Csg. Spot  
set w/ 200 Sax Cement.

7" OD 24# New S. S. Csg. 2874'0" Csg. Spot  
set w/ 250 Sax cement.

Top of K. C. at 2857

2876 Little Saturation

2887 No Saturation

2890 Drilled

2900 Cored. Total Depth.

## DRILLING WELL COMPLETION REPORT

Well No. Six (6) Farm Name Wm. Letsch  
Date completed April 26, 1939  
Description NW $\frac{1}{4}$  Sec. 26-14S-13W  
County Russell, State Kansas  
Initial production 1411 bbls. Total depth 2900 feet  
Initial volume \_\_\_\_\_ cu. ft. \_\_\_\_\_ lbs. rock pressure  
Pipe Line Company \_\_\_\_\_  
Gas Company \_\_\_\_\_  
Remarks: MCPC Interest - All  
Daily Allowable - 19.33 bbls.

*Combs*

Accounting Dept. (3)  
Rental Dept.  
Scouting Dept.   
Engineering Dept.  
Legal Dept.  
Lease Inventory Man  
Tax Dept.  
Geological  
File