

Company W. M. Wells

Farm Bell

No. 7

15-28-18E
Sec. 15- T. 28 R. 18 E
Loc. West side SE 1/4
County Neosho

Total Depth 960


Comm. Dec 1942

Comp. Jan 1943

Shot or Treated Shot 812-844

Contractor Taylor & Sons

Issued



Elevation 992 GL T&P

Production

Casing

20 in.	10 in.
151/2	81/4
121/2	65/8
133/8	53/16

Figures Indicate Bottom of Formation

1	soil	1
8	clay	9
77	shale	86--lots water 16-18'
59	lime	145
6	shale dark	151
6	lime	157
10	shale dark	167--HFW
23	shale light	190
27	lime	217
5	shale	222
10	lime	232
12	shale dark	244--water-gas
61	lime	305
61	shale	366
4	lime	370
5	shale	375
16	lime	391
4	shale	395
10	lime	405
71	shale	476--gas
49	lime	525--water 4 bph
45	shale	570--SLM
20	lime	590
8	slate black	598
5	lime	603
102	shale	705
2	lime	707
102	shale	809
40	oil sand	847
113	shale	960

plugged back to 844.
shot 812-844