KANSAS CORPORATION COMMISSION


WELL RECORD

22-16-26W
L

API# 15-135-20,571

File

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Locate well correctly

Lease Name: Evel "I" Well No. 1
Well Located: C SE SE
Ness County SEC 22 TWP 16S RGE 26W
Operator: Pickrell Drilling Company
Address: 705 Fourth National Bank Bldg., Wichita, Kansas
Elevation: Ground 2626 D.F. 2628 K.B. 2631
Type Well: (Oil, gas, dry hole) Oil

Drilling Commenced: 2/9/ 19 72 Drilling Completed: 2/19/ 19 72
Well Completed: 3/14/ 19 72 Total Depth 4575'
Initial Production: 83 BOPD

Casing Record

Size: 8-5/8" Set at 266' Size: Set at
Size: 5-1/2" Set at 4564' Size: Set at

Liner Record

Size: Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
8-5/8"	150	3/2
5-1/2"	160	50-50 pozmix 4% gel, common

Perforations

Formation	Perforated Interval and Number Shots
Miss.	OH - Acidized

RECEIVED
STATE GEOLOGICAL SURVEY OF KANSAS
MAY 1972

Electric Log Run (Show type log and depths covered)

Electra - GR-N, Guard-Cal.

API # 15-135-20,516

22-16-26W

FORMATION, TESTING AND COMPLETION RECORD

Pickrell
#1 Evel "I"

Formation	Top	Bottom
Sandy Clay	0	40
Clay - Post Rock	40	100
Shale, Sand Streaks	100	270
Shale	270	875
Sand	875	915
Shale	915	955
Sand	955	990
Shale - Shells	990	1300
Shale	1300	1490
Sand	1490	1750
Shale	1750	2038
Anhydrite	2038	2083
Shale	2083	2310
Lime & Shale	2310	2800
Lime	2800	3340
Lime & Shale	3340	3560
Shale & Lime	3560	3900
Lime	3900	4518
Lime - Chert	4518	4555
Lime, RTD	4555	4575

Show Drill Stem Tests, Well Stimulation and Production Tests

DST # 1 4430-80: Open 1/2 hr., weak blow 5 mins. Flushed, rec. 15' mud, no show. IBHP 852#/30", FBHP 529#/30", IFP 42#, FFP 53#.

DST # 2 4560-75: Open 2 hrs., strong blow throughout, Rec. 180' gas in pipe & 1680' total fluid. 1500' clean gassy oil, 180' muddy oil, no water. IBHP 1259#/30", FBHP 1113#/60", IFP 63#, FFP 644#.

Electric Tops:	Depth
Anhy	2032
Hub	3910
Tor	3926
Tans	3951
BC	4125
Stark	4197
Marm	4296
Pawn	4386
Ft Sc	4454
Cher	4478
Miss Lm	4552
Miss Dol	4561
LTD & RTD	4575

RECEIVED
STATE GEOLOGICAL SURVEY OF KANSAS
MAY 1 1972