

#1 Jennison

31-16-26W
15-135-20,94P
DESCRIPTION: NW NW SE
Section 31-16S-26W
Ness County, Kansas

LOG RECORD:
302.73' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling Company
COMMENCED: September 27, 1974
COMPLETED: October 10, 1974

TOTAL DEPTH:
4625'

FORMATION

FROM

TO

REMARKS

Clay	0	30	Ran 302.73' of used 8-5/8" surface casing; set and cemented at 306.73' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 1:15 A. M. September 28, 1974.
Sand	30	320	
Shale	320	780	
Shale & Red Bed	780	1405	
Shale	1405	1464	
#1 Anhydrite	1464	1475	
Shale	1475	1590	
Sand	1590	1800	
Shale	1800	2405	
Shale & Lime	2405	4625	

ROTARY TOTAL DEPTH: 4625'

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1974
CONSERVATION DIVISION
Wichita, Kansas

Ran electric log.

New 4 1/2" casing set and cemented at 4362' with 125 sacks of common cement, salt saturated. Plug down at 11:45 A. M. October 10, 1974.



STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

sworn to before me this 11th day of October, 1974.

