
20-28S-18E

JAMES E. GUINOTTE

GEOLOGIST – OIL PRODUCER
9½ EAST MAIN
P. O. BOX 2
CHANUTE, KANSAS

OFFICE HE 1-4130
RES. HE 1-4028



May 27, 1966

K-K Drilling Company
Box 556
Chanute, Kansas

Re: K-K Drlg. Co. CT#3 Converse
NE SE SE - Section 20-28S-18E
Neosho County, Kansas

Gentlemen:

Samples and drilling time were examined from 950 feet to R.T.D. of 1074 feet. No Electric, or Open Hole Logs were run.

Comm. Drlg: 5-24-66
Comp. Drlg: 5-27-66

Elevation: 968 Gd level

Surface Csg: 7" @ 15'

Contractor: K-K Drlg Co.
Chanute, Kansas

GEOLOGICAL TOPS	Sample and/or Time Log
Oswego ls	581 (≠ 387)
Burgess sd	1045 (- 77)
Mississippi ls	1048 (- 80)
TOTAL DEPTH	1074 (- 106)

POROUS ZONES, STAINING & TESTS

Burgess Sand

1045 - 48 - Sand fine grained gray with chert - no stain - no odor

Mississippi lime

1048 - 56 - Gray dense lime with pyrite and gray chert - no stain - no odor

1056 - 68 - Gray crystalline lime with chert - fair to good porosity - slight stain dead oil - no odor

20-28-18E

K-K Drilling Company
Chanute, Kansas

CT#3 Converse

1068 - 70 White dense lime with dolomite - no stain - no odor

1070 - 74 White crystalline lime and dolomite - good porosity - slight stain dead oil - very slight odor

REMARKS

Top of the Mississippi lime on CT#3 ran 20 feet lower than on Converse CT#2, and 21 feet lower on the Oswego lime. Due to the absence of any shows it is recommended that the well be plugged and abandoned.

Respectfully submitted

James E. Guinotte

JEG/vl