

COPY WELL RECORD

API:15-133-25,452

Well No. W-2 Farm Taylor

Producer Lancer Oil Inc.

Location 165'fsl 2700fel SE SE SW

Sec. 23

Twp. 28

Rg. 18

Elevation

State Kansas

County Neosho

Kind (Oil, Gas, Water, Dry Hole)

Contractor Fleming Drilling, Inc.

Producing formation

Top

Bottom

Shot with

qls.

from

to

Packer Set at

Kind

Size

Liner

from

to

Perforated from

to

LOG

Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
2	top Soil	2	38	Shale	651
6	clay	8	1	Lime 2'	652
2	Lime	10	80	Shale	732
6	shale	16		Cored:	
2	Lime	18	1	Lam Oil Sand & shale	
2	shale -surface	20			736
20	shale	30	10	Sand/shale	746
26	Lime	126	1	Coal	Coal
14	shale, sandy	140	8	Shale	755
26	Lime	166		Drilled:	
8	shale	174	15	shale	770
12	lime	186		Cored:	
2	shale	188	2.5	Limey sand	772.5
64	Lime	252	9.5	oil Sand	782
49	shale	301	3	shale.	785
27	shale	328	3	Lam Oil Sand	788
26	Lime	354	2	Sand, shaley	790
6	shale	360		Drilled:	
2	Lime	362	4	sand, lt odor	794
70	Shale	432	5	shale, sandy	799
5	Lime	437	15	sand,lt odor	814
7	Shale	444	27	shale, sandy	841
36	Lime	480			
41	Shale	521			
22	Lime	543			
8	Shale	551			
5	Lime	556			
25	shale	581			
29	shale	610			
3	Lime	613			

Total Depth 841'

Open Hole set 20' of 7" pipe for surface
cemented with 4 sacks cement.

Casing at

Casing at

Casing at

Cement Ran 836' of 2 7/8" pipe with
floatshoe on bottom, SN at 769'

Tubing Cent# 1,3,5,8th jt.

Rods

Additional Information

Started 5/13/92

Completed 5/19/92

RECEIVED

STATE COOPERATION COMMISSION

AUG 31 1992

CONSERVATION COMMISSION

Date Completed

O. K.

Superintendent