


DRILLING WELL COMPLETION REPORT

Well No. **One (1)** Farm Name **Letsch, Wm.**
Date completed **August 2, 1937**
Description **NW $\frac{1}{4}$ Sec. 26 - 14S- 13W**
County **Russel**, State **Kansas**
Initial production **2991** bbls. Total depth **2398** feet
Initial volume _____ cu. ft. _____ lbs. rock pressure
Pipe Line Company _____
Gas Company _____
Remarks: **Mid-Continent Petroleum Corporation interest - all**
Mid-Continent - Operators
Potential 2991 Allowable not available.



- Accounting Dept.
- Rental Dept.
- Scouting Dept.
- Engineering Dept.
- Legal Dept.
- Lease Inventory Man
- Tax Dept.
- Geological
- File

PLUG BACK
DRILLING WELL COMPLETION REPORT

Well No. 1 Farm Name William Letsch

Date completed Sept. 15, 1952

Description 1/4 Sec. 26-11S-13W

County Russell State Kansas

Old T.D. 2855

Initial production DRY bbls. Total depth P.B. 2300 feet

Initial volume _____ cu. ft. _____ lbs. rock pressure

M.C.P.C. Interest 100%

Remarks: Plugged off Lancing Lime and tested Tarkio Sand.

A. E. Pierce

Mr. McDowell
Accounting Dept. 4
Scouting Dept.
Geological Dept.
Pipe Line Dept.
Materials Dept.
Rental Dept.
Legal Dept.
Mr. Leo Meyer
Engineering Dept.
Lease Inventory
Income Tax Dept.
File

MID-CONTINENT PETROLEUM CORPORATION

WELL RECORD WILLIAM LETSCH NO. 1

NW $\frac{1}{4}$ Sec. 26-14S-13W, Russell County, Kansas
 330' from South line, and 330' from West line
 Drilling commenced 6-27-37. Drilling completed 7-26-37.
 Production: 2991 bbls.
 Drilling Contractor: Mac & Stauffer Drilling Company

FORMATION RECORD

Sand	0	30
Red bed	30	85
Shale	85	116
Sand	116	130
Lime	130	138
Shale & shells	138	250
Shale	250	639
	639	695
Shale	695	970
Lime	970	985
Shale	985	1040
Salt	1040	1365
Shale	1365	1491
Shale & lime	1491	1677
Lime	1677	1725
Lime, broken	1725	1786
Lime, hard	1786	1818
Lime	1818	1859
Shale & lime	1859	1943
Shale	1943	2056
Lime	2056	2097
Shale	2097	2110
Lime	2110	2174
Lime, broken	2174	2328
Lime, hard	2328	2430
Lime, broken	2430	2440
Lime	2440	2512
Lime, broken	2512	2548
Lime	2548	2610
Shale	2610	2625
Lime	2625	2655
Lime	2655	2805
Shale	2805	2830
Shale, black	2830	2850
Lime, K. C.	2850	2858
Shale	2858	2860
Lime, K. C.	2860	2865
Lime, K. C.	2865	2888
Lime, K. C.	2888	2894
Lime, K. C., hard	2894	2895
		Bottom

CASING RECORD

Size	Casing Spot	Cement
13" OD 40#	235'	200
7" OD 24#	2851'	250