

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

plotted in


5-10-21E

Company - TRAWVER ET AL
Farm - Farrar No. 1.

SEC. 5 T. 10 R. 21 E
C NE SW

Total Depth. 1488'
Comm. 5-26-44 Comp. 6-8-44
Shot or Treated.
Contractor. S.R. McKinney
Issued. 8-12-44

County. Leavenworth
KANSAS



CASING:
10" 32'
8 1/4" 704'
65/8" 1302'

Elevation. 933 *Co. Engr.*

Production. Dry

Figures Indicate Bottom of Formations.

soil & clay	22	red bed	910
sand & gravel	29	shale	950
shale	30	shale brwn grn	960
lime <i>Haskell</i>	84 ⁴	shale dk	980
shale	223	sand	984
lime	228 ⁵	shale	1045
shale	231 ³	sand 6BWPH	1070
lime	242 ¹¹	shale sdy	1220
shale <i>Eudora</i>	246 ⁴	shale gy	1227
lime	252	shale dk	1241
shale	264	sand <i>Mcl</i>	1254
lime	266	shale gy	1291
shale	273	sand <i>Mcl</i>	1294
lime	295	lime	1400
shale	315	lime <u>sh oil</u>	1406
lime	327	lime	1438
shale	468	lime <u>sh oil</u>	1443
shale	368	lime	1483
lime	403	lime	1488
shale	408	Total Depth.	
lime	418		
shale	430	little wtr 1443-48	
lime	445		
shale	456	gas @ 705	
lime	459	@1337	
shale	465	@1469	
lime	468		
shale	474		
lime	499		
shale	504		
lime	530		
shale	533		
lime <i>BKC</i>	548		
shale	562		
sand <i>KBT</i>	566		
shale	650		
sand little wtr <i>Hep</i>	662		
shale red & grn	670		
lime	672		
shale grn rotten	703		
lime <i>SLM 705</i>	710		
shale	716		
shale sdy	722		
sand	738		
shale	744		
lime	748		
shale	757		
lime	760		
shale	768		
lime <i>BFS</i>	770		
shale	795		
sand little wtr <i>Sq</i>	807		
shale	832		
lime	834		
shale	860		
sand <i>3BWPH</i>	870		
shale	895		
lime	898		
shale	905		