

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BEAUMONT PETROLEUM CO.
Farm - Wilbur Shinn No. 4

SEC. 19 T. 29 R. 8E
SW NE NE

Total Depth. 2784'

County. Butler

Comm. 7-20-47


Comp. 8-27-47

KANSAS

Shot or Treated. Acid. W/500 gals 8-30-47, Acid. W/1100 gals. 10-8-47

Contractor.

Issued. 11-13-48



CASING:

10" 19' 5 1/2" OD 2770'

Elevation. _____

Production. 20 Bbls.

Figures Indicate Bottom of Formations.

cellar	5
clay & lime	20
lime & shale	195
shale, lime & red bed	650
shale & lime	755
shale & shells	850
shale & lime	925
sand	937
lime & shale	950
lime, shale brk	1030
shale & lime	1095
shale & shells	1175
shale, lime shells	1395
shale & shells	1500
shale	1555
shale & lime	1705
shale, lime shells	1760
shale	1994
K. C. lime	2110
lime	2115
shale & lime	2215
shale, lime shells	2305
shale & lime	2445
lime	2473
shale & lime	2545
shale	2744
shale, chert lime	2746
lime RTD	2770
lime rainbow	2772-74
lime 1st free oil	2776-77
lime more free oil	2778-79
lime	2783-84
Total Depth	

Tops:

K. C. Lime	2110
Miss. Chert	2744
Miss. Lime	2746

Oil Shows:

Odor Oil	2070
1st Free Oil	2776-77
More Free Oil	2777-84

Rotary table 3'10" above
ground level. Cable Rig
floor 1'10" above ground
level.

5 1/2" OD - 11 1/2 Smls. - 60 Sx.
(8-5-47)