


MCLAUGHLIN ET AL
Meyers No. 1.

SEC. 5 T. 10 R. 21 E
CSE SE

Total Depth. 1446'
Comm. 8-21-43 Comp. 9-20-43
Shot or Treated.
Contractor. Dave Wilson
Issued. 11-13-43

County. Leavenworth



CASING:
10" 22'
8" 647'
65/8" 900'
53/16" 1396'

Elevation. 905 H. H.

Production. Dry

Figures Indicate Bottom of Formations.

surface	4	lime	750
shale	50	shale	757
sand	110	lime	762
sdv shale	140	shale	765
shale	180	lime <i>BTS</i>	769
lime	184	shale	775
shale	189	sand ✓	785
lime	201	shale	805
shale	204	shale sdv	865
lime	210	shale lt	895
shale	225	shale blue	900
lime	228	hole caving	
shale	230	shale	912
lime	250	shale dk	940
shale	275	shale lt	970
lime	288 ¹³	shale blue <i>LEW@985</i>	980
shale	327 ³⁹	shale blk	990
lime	350 ²³	shale	1025
shale	353 ³	lime	1028
lime	357	shale	1035
shale	372	sand ✓	1050
lime	379	shale dk	1075
shale	396	shale sdv L.	1125
lime	408	shale D.	1155
shale dk	422	shale	1195
lime	426	shale blk	1210
shale dk	430	sh white	1219
lime	432	shale blue	1227
shale	435	ls or hd sand ✓	1231
lime	440	shale	1235
shale	442	shale D.	1252
lime	463	oil sand <i>Mcl</i>	1265
shale dk	467	shale dk	1300
lime	490	Miss. lime	1343
shale	495	coal	1345
lime	499	lime	1350
shale blk, some wtr	502	slate blk	1353
lime	514	lime	1417
shale	525	chert smell oil	1419
wh lime shale <i>BKC</i>	540	lime & shale shell	1425
shale	623	lime	1440
red rock	625	wtr sand <i>HFV</i>	1444
shale sdv	640	lime	1446
red rock	642	Total Depth.	
shale	650		
lime	654		
shale	670	smell oil 1252-56 <i>McLouth Sd.</i>	
lime	677	wtr 1343-55 hole caving	
shale	680		
lime	682		
shale	689		
lime	691		
shale lt sdv	700		
wtr sand	718		
lime hd	720		
shale dk	732		
lime	735		
shale	746		