


Company - MARGAY OIL CORPORATION
Farm - G. E. Bengston No. 1.

SEC. 3 T. 16 R. 3 W
CSW NW
3-16-34

Total Depth. 3366
Comm. 4-5-44 Comp. 5-4-44
Shot or Treated.
Contractor.
Issued. 7-1-44

County. Saline
KANSAS



CASING:
8 5/8" 309' Cem.
5 1/2" 3360' Cem.

Elevation. _____

Production. Pot. 8 B.
plus 5 BW

Figures Indicate Bottom of Formations.

shale and shells	250
gravel	260
lime shale	270
lime	310
lime and shale	355
lime anhydrite	365
red bed	380
lime & shale	620
sand	635
lime	650
lime streaks shale	700
sandy lime	735
shale & lime	1210
shale and shells	1700
lime	1720
lime & shale	1950
lime streaks of shale	1965
shale and lime shells	2020
shale and lime	2080
lime	2105
lime & shale	2250
lime broken	2295
lime	2350
lime & shale	2400
lime streaks of shale	2455
shale & lime	2540
shale & shells	2554
shale & lime	2620
shale & shells	2693
shale & lime	2826
cherty lime	2877
shale	2887
lime	3003
lime & shale	3260
shale	3302
shale & lime	3361
lime Viola	3366
Total Depth.	

Tops:
K.C. Lansing 2160
Miss. 2798
Maquoketa Dolomite 3298
Sylvan Shale 3340
Xlyn Viola White 3350
Pay Zone 3361-63