


Plotted
27-10-21E

Company - HUISMAN-NEWLAND
Farm - Bachelor No. 1.

SEC. 27 T. 10 R. 21 E
CE₂ SE SE

Total Depth. 1216'
Comm. 11-3-43 Comp. 11-24-43
Shot or Treated.
Contractor. Arch Newland
Issued. 1-8-44

County. Leavenworth
KANSAS



CASING:
12" 30'
8" 610'

Elevation. *905 H.H.*

Production. Dry

Figures Indicate Bottom of Formations.

soil	2	shale lt	910
clay yellow	10	lime	915
shale blue	113	shale blk (gas @ 925)	935
lime	130 <i>KRC</i>	shale lt	970
shale	133	shale wh	1000
lime	147	shale lt	1020
shale	150	shale blue	1125
lime	155	shale dk brown	1135
shale	175	shale blk	1150
lime	194	shale lt	1158
shale brown	202	shale dk	1173
shale blue	212	shale lt	1180
lime	235	shale blue	1185
shale	255	shale lt & sdy	1192
lime	280	shale dk	1205
shale	297	lime sdy	1215
lime	305	sh dk & lime (gas)	1216 <i>= M</i>
shale	310	Total Depth.	
lime	312		
shale	318		
lime	327		
shale lt	340		
lime	355		
shale	365		
lime	367		
shale dk	371		
lime	406		
shale wtr	410		
lime	438		
shale dk wtr	440		
lime	460 <i>BRC</i>		
shale lt	525		
shale blue (gas @ 551)	560		
lime <i>BRC</i>	572		
shale gy	585		
red rock	600		
shale	612		
lime	622		
shale	650		
shale lt	670		
lime wtr	672		
shale blue	675		
lime	695		
shale dk	715		
lime & shells	720		
shale dk	735		
lime sdy	750 <i>CH</i>		
wtr sand	760		
shale dk	830		
lime	840		
shale lt	860		
lime	863		
shale blk	867		
lime <i>BFS</i>	869		
shale dk	900		

1205
9'