

19-29-8E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEAUMONT PETROLEUM COMPANY
Farm- Wilbur Shinn No. 18

SEC. 19 T. 29 R. 8E
C NE/4

Total Depth. 2819 PB 2810
Comm. 12-29-55 Comp. 2-6-56
Shot or Treated.
Contractor.
Issued. 8-11-26

County Butler
KANSAS



CASING:

10 3/4" 30' cem w/25 sx.
7" 2781' cem w/135 sx.

Elevation. 1566 RB

Production. 25 BOPD

lime	26
red bed	30
lime	80
lime, shale brks	720
shale, lime strks	970
shale	1010
lime, shale brks	1300
shale, lime strks	1715
shale	1825
lime	1865
shale, lime strks	1997
lime	2230
shale	2326
lime	2347
shale	2395
lime	2476
shale	2490
shale, lime strks	2600
shale, lime	2700
shale	2739
lime RTD	2781
Cable Tool	
shale	2819
Total Depth	
Plugged back to	2810

Figures indicate Bottom of Formations.

ROTARY BUSHING 5'6" ABOVE GROUND LEVEL

Tops: Scout
Kansas City 1997
Mississippi 2750