

PHONE: URBANA 920

TAYLOR & SONS

DRILLING CONTRACTORS

State Geological Survey
WICHITA BRANCH
26-28-18E
EARLTON, KANSAS p1

Well Record

Well No. 44 Farm Taylor River Producer Taylor Bros
 Location Sec. 26 Twp. 23 Rg. 18
 Elevation 1495 from N line 2030 from N line State Kansas County Neosho
 Kind (Oil, Gas, Water, Dry Hole) Oil Contractor Taylor Bros
 Producing formation Eastonville Top 758 Bottom 779
 Shot with _____ qts. from _____ to _____
 Packer set at 718 Kind Rag Size 5"
 Liner from _____ to _____ Perforated from 721 to 724

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
1	soil	1			
12	clay B	13			
19	shale	32			
57	lime	89			
43	shale	132			
24	lime	156			
7	shale	163			
12	lime	175			
14	shale	189			
55	lime	244			
62	shale	306			
42	lime	348			
72	shale	420			
48	lime	468			
43	shale	511			
18	lime	529			
7	shale	536			
5	lime	541			
25					
59	shale	600			
9	sand	609			
39	shale	648			
2	lime	650			
22	shale	672			
11	oil sand	726			
32	shale	758			
21	oil sand	779			

RECEIVED
 STATE COMMISSION
 JUL 13 1983
 CONSERVATION DIVISION
 WICHITA, KANSAS

Total Depth 779
 Open Hole
 Casing 9 5/8 at 20 ft
 Casing 7 5/8 at 247
 Casing 5 1/2 at 645
 Cement 2 ft to bottom 120 lb
 Tubing 2 3/8 759'
 Rods
 Additional Information
 packer set above lower sand treated open hole
 perforated 718-722
 Propped standing valve in seating nipple treated
 thorough perforations

Date Completed June 3 1983 O. K. Superintendent