

# TAYLOR & SONS

DRILLING CONTRACTORS

EASTON, KANSAS

Chanute

PHONE: ~~URBANA 920~~

314 763 2318

## Well Record

State Geological Survey  
MICHITA BRANCH

Well No. 46 Farm Joyler Bros Producer Joyler Bros  
 Location 2295' from N' line Sec. 26 Twp. 28 Rg. 18 E  
 Elevation 2410' from W line State Kansas County Neosho  
 Kind (Oil, Gas, Water, Dry Hole) \_\_\_\_\_ Contractor Joyler Bros  
 Producing formation Bartheville Top \_\_\_\_\_ Bottom \_\_\_\_\_  
 Shot with 7/8 qts. from 721 783 to 739 801  
 Packer set at 718 Kind Rag Size 5"  
 Liner from \_\_\_\_\_ to \_\_\_\_\_ Perforated from \_\_\_\_\_ to \_\_\_\_\_

### LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	soil	2			
10	clay	12			
28	shale	40			
50	lime	90			
54	shale	144			
22	lime	166			
7	shale	173			
17	lime	190			
14	shale	204			
50	lime	254	7"	256	
58	shale	312			
46	lime	358			
70	shale	428			
52	lime	480			
39	shale	519			
21	lime	540			
7	shale	547			
5	lime	552			
59	shale	611			
2	sand	613			
36	shale	649			
2	lime	651	5"	653	
70	shale	721			
18	oil sand	739			
42	shale	783			
18	oil sand	801			

Total Depth 801  
 Open Hole ~~878~~  
 Casing 8 7/8 at 20ft  
 Casing 7 5/8 at 256ft  
 Casing 5 1/2 at 653ft  
 Cement Top to bottom  
 Tubing 2 3/8" 784  
 Rods \_\_\_\_\_  
 Additional Information \_\_\_\_\_

*packer set above  
lower sand treated  
open hole.*

*perforated @ 726-29*

*Dropped seating nipple  
Dropped standing  
Valve in seating  
Nipple. Frac.  
Then perforation*

Date Completed December 10 1983 O. K.

Lewis R. Joyler  
Superintendent