

COPY WELL RECORD

Well No. 70 Farm Taylor Producer Lancer Oil Inc.

Location 4450fs1 3110fel SE NE NW Sec. 26 Twp. 28 Rg. 18

Elevation State Kansas County Neosho

Kind (Oil, Gas, Water, Dry Hole) Contractor Fleming Drilling, Inc.

Producing formation Top Bottom

Shot with qts. from to

Packer Set at Kind Size

Liner from to Perforated from to

LOG					
Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
2	top soil	2	80	shale	712
6	clay	8		Cored:	
10	shale	18	11	shale	723
3	Lime, surface	21	1	Coal	724
51	Lime	72	8	shale	732
6	shale	78	7	Drilled:	
4	Lime	82		shale	739
4	shale	86	2	sand/shale	741
55	Lime	121		Cored:	
28	Lime	149	18	sand, lt.	759
10	shale	159	10	Oil sand	769
42	Lime	201	2	Oil Sand, drk.	771
35	Lime	236	1	shale	772
58	Shale	294	2	Drk sand, Oil	774
17	Lime	311	26.5	Oil sand	800.5
12	Shale	323	.5	shale	801
11	Lime	341		Drilled:	855
70	shale	411			
5	Lime, 40'	416			
6	shale	422			
38	Lime	460			
41	Shale	501			
20	Lime, 20'	521			
1	Lime	522			
9	shale	531			
6	Lime, 5'	537			
53	Shale	590			
2	Lime	592			
39	Shale	631			
1	Lime, 2'				

Total Depth 855'

Open Hole 21' of 7" cemented with 4 sack
Casing Cement. at

Casing at

Casing at

Cement Ran 849' of 2 7/8" pipe with
Tubing floatshoe on bottom. SN# at 756'

Rods Cent# 1st, 4th, 6th and 9th jt.

Additional Information

Started 6/17/92

Completed 6/26/92

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1992
CONSERVATION DIVISION
Wichita, Kansas

Date Completed O. K. Superintendent