

26-28-18E

WELL RECORD COPY

API: 15-133-25,448

Well No. P 6 Farm Taylor Producer Lancer Oil Inc.

Location 4950fsl 2970fel NE NE NW Sec. 16 Twp. 28 Rg. 18

Elevation State Kansas County Neosho

Kind (Oil, Gas, Water, Dry Hole) Contractor Fleming Drilling, Inc.

Producing formation Top Bottom

Shot with qts. from to

Packer Set at Kind Size

Liner from to Perforated from to

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
2	top soil	2	11	shale	640
6	clay	8	1	Lime, 2'	641
2	Lime	10	20	shale	661
10	shale, surface	20	61	shale	732
5	shale	25	3	shale, sandy	735
18	lime	89	18	shale	753
27	shale	116		cored:	
4	Lime	120	2.5	Limey sand	755.5
5	Shale	125	3.5	sand	759
33	Lime	158	6	shale	765
8	shale	166	3	Oil Sand	768
75	Lime	241	10	sand shale	778.
4	Lime	245	2.5	Limey sand	780.5
57	shale	302	11.5	sand shaley	792
16	Lime	318	61	shale	732
13	shale	331	3	shale, sandy	735
15	Lime	346	18	shale	753
76	shale	422		cored:	
5	Lime, 40'	427	2.5	limey sand	755.5
7	shale	434	3.5	sand	759
37	Lime	471	6	shale	765
39	shale	510	3	Oil sand	768
21	Lime, 20'	531	10	sand, shaley	778
8	shale	539	2.5	limey sand	768
2	Lime, 5'	541	11.5	sand, shaley	792
3	Lime	545		cored:	
16	shale	599	16	sand	808
3	Lime	602	3	shale	811
16	shale	618		Drilled:	
1	Lime	619	19	shale	830

Total Depth 835'

Open Hole set 20' of pipe for surface

Casing Cemented with 4 sacks cement.

Casing at

Casing at

Cement Ran 826' of 2 7/8" pipe with float

Tubing shoe on bottom. SN# 762' cent# 1,

Rods 5th and 8th jt.

Additional Information

Started 6/24/92

Completed 7/8/92

REIVED

STATE COMMISSION

1 1992

CONSERVATION DIVISION

5 shale 835'

Date Completed O. K. Superintendent